

Addendum 1: Coroners/Evidence Building Demolition Project #30-9075

Please note the following changes to the bid document issued for the above project.

Change #1-

Scope-

1.1 SUMMARY

A. Section includes:

1. Demolition and removal of building and foundation(s).
2. Concrete Slab to remain.

To be replaced with:

1.2 SUMMARY

B. Section includes:

1. Demolition and removal of building.
 - A. Remove two (2) existing vehicle floor hoists, and fill excavated area with satisfactory soil materials and or CDF to match existing slab.
2. Concrete Slab to remain.

Clarification-

1. Concrete slab shall be left in place. Rebar or any other supporting system shall be removed, or made smooth to match existing slab.
2. Slab height on East side of building shall remain current height.
3. Glue and or adhesive shall be removed from slab.
4. Southern Guardrail in parking lot to be retained for future use. Remove and store.
5. Meters and bases remove shall be returned to owner.